Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02250416 Call Order: 004 Proposal: E21M2 District:02
Counties: DUVAL
Road Name: SR105 HAULOVER CREEK BR NO720063 - BR PAINTING
Limits: 72260000
Project(s): 43556515201(*) Federal Aid No: N/A

Total Roadway Length:	0.042 Miles	Contract Days:	150
Total Bridge Length:	0.042 Miles	Letting Date:	04/16/25
Total Proposal Length:	0.084 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120 Days (acq. time)

Proposal Budget Estimate: $622,239.00

Please read the full advertisement

Description:

(SR 105 (Heckscher Dr) at Haulover Creek Bridge No. 720063) The Improvements under this Contract consist of concrete spall repair, concrete cracking repair, steel coating and incidental construction for Bridge No. 720063 at SR 105 over Haulover Creek in Duval County. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Call Order: 004 Proposal: E21M2

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	500.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	27.500
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	1.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	35.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43556515201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43556515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43556515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,050.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	300.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	88.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43556515201)	LS	1.000