

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02250416	Call Order: 005	Proposal: E21O3	District:02
Counties:	ALACHUA			
Road Name:	SR26 AT HATCHET CREEK BRIDGE #260033			
Limits:	26130000			
Project(s):	20776125201(*)	Federal Aid No: N/A		
Total Roadway Length:	2.018 Miles	Contract Days:	250	
Total Bridge Length:	0.038 Miles	Letting Date:	04/16/25	
Total Proposal Length:	2.056 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days (acq. time)	
Proposal Budget Estimate:	\$2,986,525.00			

Please read the full advertisement

Description:

(SR 26 at Hatchet Creek Bridge #260033) The Improvements under this Contract consist of bridge work including installing crutch bents on prestressed concrete piles, temporary work structure, drainage improvements, scour countermeasures (gabion mats), guardrail, and other incidental construction at SR 26 Bridge No. 260033 over Hatchet Creek in Alachua County. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 005 Proposal: E2103

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	141.300
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	23,513.000
	0455- 15- 16	PREFORMED PILE HOLES, 36" TO 43" DRILL/PUNCH SIZE	LF	216.000
	0455- 15- 26	PREFORMED PILE HOLES CASING, 36" TO 43" DRILL/PUNCH SIZE	LF	216.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	6.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	360.000
	0455-115-	PILE REDRIVE	EA	6.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	6.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	6.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (20776125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20776125201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	56.000
	0102- 60-	WORK ZONE SIGN	ED	2,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,000.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	528.000
	0103- 1-100	TEMPORARY WORK STRUCTURE (20776125201)	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,507.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	911.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (20776125201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (20776125201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (20776125201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (20776125201)	LS	1.000
	0120- 5-	CHANNEL EXCAVATION	CY	753.000
	0120- 6-	EMBANKMENT	CY	774.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.900
	0530- 5- 11	GABION, MATTRESS LESS THAN 1 FOOT THICKNESS	SY	868.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	44.000
	0536- 73-	GUARDRAIL REMOVAL	LF	45.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,079.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	626.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20776125201)	LS	1.000