

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02250416 Call Order: 010 Proposal: Z2258-R0 District:02
 Counties: CLAY, DUVAL, NASSAU, PUTMAN, ST JOHNS
 Road Name: Pre-Event Emergency Sign Permanent Repair and Replacement(E)
 Limits: Midpoint
 Project(s): 4465923D212(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: 365
 Total Bridge Length: 0.000 Miles Letting Date: 04/16/25
 Total Proposal Length: 0.000 Miles Contract Execution Days: 5
 Special Start Date: N/A
 Aquis/Flexible Start Time: 00 Days (acq. time)

Proposal Budget Estimate: \$0.00

Please read the full advertisement

Description:

The purpose of this Contract is to provide Sign Repair and Replacement Operations, including permanent repairs, pursuant to a Governor's and/or President's Declaration of a State Emergency. This Contract will be a regional contract that includes Eastern counties: Clay, Duval, Nassau, Putnam and St. Johns counties within District 2. The Contractor shall perform Sign Repair and Replacement Operations pursuant to the terms of this Contract and at the direction of the Department. District boundaries are as described on the Agency Resources Website at the following URL: <http://www.fdot.gov/agencyresources/districts/>

The Contractor shall provide a letter to the Department at the time of bid, from a surety authorized to do business in the state of Florida, verifying the Contractor is bondable in the state of Florida. For the purposed of this contract, the dollar amount is established at \$500,000.00.

Awarded Contractor must execute documents within five (5) calendar days, excluding Saturdays, Sundays, and state holidays with General Liability and Workers Comp Insurance.

No quantities are guaranteed and there will be no unit cost adjustment for quantities required over or under the estimated quantities.

RENEWAL OPTION. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Call Order: 010 Proposal: Z2258-R0

ALT	Item	Description	Unit	Quantity
Section 0001 EMER.DELINEATOR/ATTENUATOR/SIGN REPR(EA)				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	3.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	3.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	3.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	3.000
	0634- 4-142	SPAN WIRE ASSEMBLY, F&I, SINGLE POINT, DIAGONAL	PI	3.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	3.000
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	3.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	3.000
	0639- 1-113	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER NOT REQUIRED	AS	3.000

Call Order: 010 Proposal: Z2258-R0

ALT	Item	Description	Unit	Quantity
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	3.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	3.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0641- 2- 15	PRESTRESSED CONCRETE POLE, F&I, TYPE P-V	EA	3.000
	0670- 4- 1	INTERSECTION CONTROL BEACON CONTROLLER ASSEMBLY, FURNISH & INSTALL	AS	3.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	57.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	19.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	4.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	4.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	5.000
	0700- 1-312	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, 12.0-20.0 SF	EA	5.000
	0700- 1-313	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 1-800	SINGLE COLUMN GROUND SIGN ASSEMBLY, REPAIR	EA	5.000
	0700- 1-870	SINGLE COLUMN GROUND SIGN ASSEMBLY, REPAIR- REPLACE POST, USE EXISTING SIGN PANEL	EA	5.000
	0700- 2-111	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	5.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	4.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	6.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	25.000
	0700- 2-117	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 200.1-300.0 SF	EA	5.000
	0700- 2-118	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 300.1-400.0 SF	EA	2.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	42.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	5.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	11.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	1.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	5.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	1.000
	0700- 3-107	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 201-300 SF	EA	1.000

Call Order: 010 Proposal: Z2258-R0

ALT	Item	Description	Unit	Quantity
	0700- 3-108	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 301-400 SF	EA	1.000
	0700- 3-109	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 401-500 SF	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	5.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	1.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	5.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	1.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	1.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	1.000
	0700- 3-210	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 501-600 SF	EA	1.000
	0700- 3-211	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 601 SF AND GREATER	EA	1.000
	0700- 3-301	SIGN PANEL, FURNISH & INSTALL SINGLE POST BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	EA	2.000
	0700- 3-302	SIGN PANEL, FURNISH & INSTALL SINGLE POST BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	EA	2.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	3.000
	0700- 3-402	SIGN PANEL, INSTALL, 12-20 SF	EA	3.000
	0700- 3-403	SIGN PANEL, INSTALL, 21-30 SF	EA	3.000
	0700- 3-404	SIGN PANEL, INSTALL, 31-50 SF	EA	3.000
	0700- 3-405	SIGN PANEL, INSTALL, 51-100 SF	EA	3.000
	0700- 3-406	SIGN PANEL, INSTALL, 101-200 SF	EA	3.000
	0700- 3-407	SIGN PANEL, INSTALL, 201-300 SF	EA	1.000
	0700- 3-408	SIGN PANEL, INSTALL, 301-400 SF	EA	1.000
	0700- 4-111	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, UP TO 20 FT	EA	1.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	1.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	1.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	1.000
	0700- 4-121	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, UP TO 20 FT	EA	1.000
	0700- 4-122	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 21-30 FT	EA	1.000
	0700- 5- 11	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	1.000
	0700-141-111	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-141-121	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/2 BEACONS, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000

Call Order: 010 Proposal: Z2258-R0

ALT	Item	Description	Unit	Quantity
	0700-141-311	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-141-321	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, W/2 BEACONS, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-141-330	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, ELECTRONIC DISPLAY SIGN	EA	1.000
	0700-141-331	ENHANCED HWY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, ELECTRONIC DISPLAY SIGN, W/UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-142-121	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/2 BEACONS, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-142-901	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE BEACON(S), SIGN TO REMAIN	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	5.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	5.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	2.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	2.000
	E700- 46- 32	REPAIR EXISTING SIGN (MULTI POST)	AS	2.000