Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02251217 Call Order: 001 Proposal: E21Q6-R0 District:02

Counties: ALACHUA, BRADFORD

Road Name: Gainesville Maintenance Outfall and Pond Mowing

Limits: Midpoint

Project(s): 41021347277(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	12/17/25
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (acq. time)

Proposal Budget Estimate: $360,000.00

Please read the full advertisement

Description:

The improvements under this work document driven contract consist of slope mowing and litter removal to maintain outfall ditches and retention ponds, including areas that may be saturated or have standing water, as listed in the bid items and appendix within state maintained right of ways in Alachua and Bradford Counties. Work will include mowing berms, slopes, pond and ditch bottoms, as well as trimming around trees, drainage structures, etc. Hand tools and power equipment such as hand trimmers and specialized mowers may be required to perform the work. All grass and vegetation will be mowed to a height of 6 inches plus or minus 1/2 inch. When determined by the Engineer, certain areas, due to location, may be cut to a height of 4 inches plus or minus 1/2 inch. Mobilization and Maintenance of Traffic and herbicide application are incidental to the pay items listed. RENEWAL OPTION.

Call Order: 001 Proposal: E21Q6-R0

ALT	Item	Description	Unit	Quantity
Section				
	E107- 1- 1	LITTER REMOVAL	AC	625.000
	E107- 2- 2	MOWING (SLOPE)	AC	625.000