

Call Order: 003 Proposal: E21Q1

ALT	Item	Description	Unit	Quantity
	0102- 61-	BUSINESS SIGN	EA	1.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	322.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,236.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	3,050.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,852.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	8.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	38.000
	0102-115-	TYPE III BARRICADE	ED	2,000.000
	0104- 10- 3	SEDIMENT BARRIER	LF	35,287.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	409.750
	0107- 2-	MOWING	AC	409.750
	0110- 1- 1	CLEARING & GRUBBING (21152215201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	13,187.300
	0120- 4-	SUBSOIL EXCAVATION	CY	14,889.600
	0120- 6-	EMBANKMENT	CY	20,198.800
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	37,622.000
	0160- 4-	TYPE B STABILIZATION	SY	30,419.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	329.000
	0285-705-	OPTIONAL BASE, BASE GROUP 05	SY	22,560.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	158.000
	0289- 1-104	COARSE AGGREGATE BASE SPECIAL DESIGN, 24"	SY	94.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	23,575.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	1,791.300
	0334- 1- 59	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, HIGH POLYMER	TN	2,047.400
	0337- 7- 26	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, HIGH POLYMER	TN	986.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	75.900
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	144.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	42.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	205.000
	0430-536-200	STRAIGHT CONCRETE ENDWALLS, 36", DOUBLE, 0 DEGREES, ROUND	EA	1.000
	0430-542-330	STRAIGHT CONCRETE ENDWALLS, 42", TRIPLE, 45 DEGREES, ROUND	EA	2.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	8.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	4.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	2,487.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	42.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	2,453.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	34.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	226.000

Call Order: 003 Proposal: E21Q1

ALT	Item	Description	Unit	Quantity
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	515.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	79.000
	0527- 2-	DETECTABLE WARNINGS	SF	220.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	37.700
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	62.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	33,140.000
	0550- 10-363	FENCING, TYPE R, GREATER THAN 10.0', WITH FULL ENCLOSURE	LF	272.000
	0550- 10-410	FENCING, WOOD FENCE, 0.0-5.0'	LF	128.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	33,140.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	40,715.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,529.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.710
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.900
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	26.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.930
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21152215201)	LS	1.000
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	41.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	8.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 15- 2	IN-STREET SIGN ASSEMBLY, FURNISH AND INSTALL- FIXED BASE CONNECTION	EA	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21152215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	149.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	301.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	26.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	32.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.150
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.070
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.070
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	191.000