Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02250521 Call Order: 004 Proposal: E21U1 District:02

Counties: ALACHUA

Road Name: FC-5 Repairs on I-75 in Alachua County

Limits: 26260000

Project(s): 45564017201(*) Federal Aid No: N/A

Total Roadway Length:	60.000 Miles	Contract Days:	45
Total Bridge Length:	0.000 Miles	Letting Date:	05/21/25
Total Proposal Length:	60.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (acq. time)

Proposal Budget Estimate: $1,329,186.00

Please read the full advertisement

Description:

The work under this site-specific, work document driven contract consists of milling and replacing open graded friction course (FC-5) on I-75 in Alachua County at specified areas as prioritized in the appendix of this contract. All milled areas shall meet the surface texture requirements described in section 327-3.1.1 of the current FDOT Standard Specifications for Road and Bridge Construction. Mobilization and Maintenance of Traffic are incidental to the pay items listed. EXPERIENCE IN ASPHALT PAVING (FORM 850-070-01) MUST BE COMPLETED AND SUBMITTED WITH THE BID. BUDGET ESTIMATE -$1,329,000.00.

Call Order: 004 Proposal: E21U1

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	24,933.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	1,059.700
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	284.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.030
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	12.121
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.439
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.496
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	5.530
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.439