

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	03250508	Call Order: 002	Proposal: E3X98	District:03
Counties:	SANTA ROSA			
Road Name:	SR 10 (US 90) - RESURFACING			
Limits:	58010000			
Project(s):	22036025201(*)	Federal Aid No: N/A		
Project(s):	22036025202	Federal Aid No: N/A		
Total Roadway Length:	11.032 Miles	Contract Days:	340	
Total Bridge Length:	0.331 Miles	Letting Date:	05/08/25	
Total Proposal Length:	11.363 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$5,001,705.00			

Please read the full advertisement

Description:

The Improvements under this District Contract for FPID 220360-2-52-01 consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb & gutter, highway signing, guardrail, pavement markings, and other incidental construction on SR 10 (US 90) from Escambia River Bridge to East of CR 197A (Woodbine Rd.) in Santa Rosa County. FPID 220360-2-52-02 consists of bridge joint replacement on Bridge Nos. 580002, 580004, 580007, 580052, and 580054.

PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT

Marine General Liability Insurance as referenced in Section 7-13.5 of the FDOT Standard Specifications may be required if any work under this Contract is performed using vessel(s)*. Prior to the Contract execution, Contractor shall provide written certification to the Department if no vessel(s) will be used for the work.

* Vessel: a watercraft or other artificial contrivance, whether motorized or non-motorized, used to perform some or all of the work, as well as any incidental work related to the project, which includes, but is not limited to, barges, dredges, mobile offshore drilling units, floating cranes, tugboats, ferries, and any watercraft used to transport construction workers, materials, or equipment at the project.

Call Order: 002 Proposal: E3X98

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	2,645.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	330.600
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (22036025201)	LS	1.000
	0101- 1-	MOBILIZATION (22036025202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (22036025201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (22036025202)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	72.000
	0102- 60-	WORK ZONE SIGN	ED	9,740.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	4,760.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	25,731.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	391.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	997.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	340.000

Call Order: 002 Proposal: E3X98

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	340.000
	0102-115-	TYPE III BARRICADE	ED	102.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,178.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	181.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	1,504.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0107- 1-	LITTER REMOVAL	AC	431.740
	0107- 2-	MOWING	AC	393.100
	0110- 1- 1	CLEARING & GRUBBING (22036025201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	98.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	204.900
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	874.800
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	25.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	46.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	9,040.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	47,099.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	11,040.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,155.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	10,375.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	208.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	955.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	9,393.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	3,035.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	762.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	116.200
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	106.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	157.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	32.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	24.000
	0530- 74-	BEDDING STONE	TN	20.700
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,483.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	875.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	8.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,963.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	7.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	13,773.000

Call Order: 002 Proposal: E3X98

ALT	Item	Description	Unit	Quantity
	0571- 1- 13	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 3	SY	2,521.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,424.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.504
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.378
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	162.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	457.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	210.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.228
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.098
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.050
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	53.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.190
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.004
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	385.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.086
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22036025201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22036025202)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	6.599
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	25.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	23.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	7.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	8.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,424.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	153.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (22036025201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	162.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	457.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	70.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.050

Call Order: 002 Proposal: E3X98

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	53.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	385.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.086
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	140.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	4.564
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.166
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	4.228
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.098
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	3.478
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.004
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.194
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.212
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.712
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.332
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.332
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.332
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.332
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	2,083.000