

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting: 04191206      Call Order: 004      Proposal: E4T84      District:04  
Counties: PALM BEACH  
Road Name: SR-A1A/ OCEAN BLVD/ HAVEN ASHE BRIDGE #930060  
Limits: 93060000  
Project(s): 43389615201(\*)      Federal Aid No: N/A  
Total Roadway Length: 0.102 Miles      Contract Days: 80  
Total Bridge Length: 0.102 Miles      Letting Date: 12/06/19  
Total Proposal Length: 0.204 Miles      Contract Execution Days:  
Special Start Date: N/A  
Aquis/Flexible Start Time: 60  
Proposal Budget Estimate: \$662,737.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of but not limited to the full removal and replacement of the existing structural steel coating system, cleaning and coating of Class-V Finish to concrete surfaces on SR-A1A/ Ocean Boulevard over Boca Inlet Bridge No. 930060 in Palm Beach County.

- Pre-Qualified: Contractor must be pre-qualified.
- PERFORMANCE BOND: A Contract / Performance bond is required for this project.

Notes:

- Acquisition Time: 60 days for Containment System Submittal and Coast Guard Notice.
- Include special provision SP0081300MID Milestone Incentive-Disincentive for Bridge Opening Incentive of \$1,440 per day for 10 days equaling \$14,400 Incentive begins June 16, 2020 and ends June 25, 2020.
- There is one (1) TSP (T465 – Movable Bridges).

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 004 Proposal: E4T84**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	12,111.000
	0465- 3- 50	MOVABLE BRIDGE COUNTERWEIGHT, ADJUST	EA	3.000
	0465- 20-	MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (43389615201 930060)	LS	1.000
	0465- 21-	MOVABLE BRIDGE OPERATOR	DA	80.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43389615201 930060)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43389615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43389615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,000.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,120.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	6.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	80.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	508.000
	0102-911- 3	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK, OTHER	SF	24.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43389615201)	LS	1.000