Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 04200103 Call Order: 005 Proposal: E4T65 District:04

Counties: PALM BEACH

Road Name: SR-704 WESTBOUND TO SOUTHBOUND SR-9/I-95 INTERCHANGE

Limits: 93220148

Project(s): 44144215201(*) Federal Aid No: N/A

Total Roadway Length:	0.171 Miles	Contract Days:	325
Total Bridge Length:	0.163 Miles	Letting Date:	01/03/20
Total Proposal Length:	0.334 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: $2,032,101.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of Removal and replacement of existing steel coating and Class V finish but not limited to, abrasive blast cleaning and painting of all existing structural steel surfaces including box girders, diaphragms, stiffeners, cross frames, connection plates, sole plates and steel bearing assemblies with a four-coat system at Bridge No. 930469 interchange along State Road 9/I-95 southbound on ramp in Palm Beach County.

Pre-Qualified: Contractor must be pre-qualified.

Performance Bond: A Contract / Performance bond is required for this project.

Call Order: 005 Proposal: E4T65

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	23,801.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	3.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44144215201 930469)	LS	1.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL (44144215201 930469)	SF	50.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44144215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44144215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,928.000
	0102- 60-	WORK ZONE SIGN	ED	15,610.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	56,791.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	3,130.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	132.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,277.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,668.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	568.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	568.000
	0999- 16-	PARTNERING, DO NOT BID (44144215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44144215201)	LS	1.000