

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04200306 Call Order: 001 Proposal: E4T88 District:04
Counties: PALM BEACH
Road Name: SR-9/I-95 NB NOISE WALL EXTENSION
Limits: 93220000
Project(s): 43986015201(*) Federal Aid No: N/A
Total Roadway Length: 0.324 Miles Contract Days: 175
Total Bridge Length: 0.000 Miles Letting Date: 03/06/20
Total Proposal Length: 0.324 Miles Contract Execution Days:
Special Start Date: N/A
Aquis/Flexible Start Time: 90
Proposal Budget Estimate: \$1,331,785.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of but not limited to, sound wall construction (extending existing sound walls), monitor existing structures (vibration, inspection and settlement), fencing, utility adjustments, embankment, and sod along State Road 9 (I-95) from approximately 0.56 miles north of Lake Ida Road for 0.591 miles in the Cities of Delray Beach and Boynton Beach, Palm Beach County.

Pre-Qualified: Contractor must be pre-qualified.

Performance Bond: A Contract / Performance bond is required for this project.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 001 Proposal: E4T88

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43986015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43986015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,575.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	175.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,725.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	850.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	25.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	189.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,200.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	8.940
	0107- 2-	MOWING	AC	7.080
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43986015201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43986015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43986015201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0120- 1-	REGULAR EXCAVATION	CY	290.000
	0120- 4-	SUBSOIL EXCAVATION	CY	6.000
	0120- 6-	EMBANKMENT	CY	422.000
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	24,640.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	14.000
	0563- 3-	ANTI-GRAFFITI COATING, SACRIFICIAL	SF	49,280.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,916.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0639- 2- 4	ELECTRICAL SERVICE WIRE, RELOCATE	LF	8.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43986015201)	LS	1.000