

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 05251202      Call Order: 007      Proposal: E58F9      District:05

Counties: LAKE

Road Name: SR 500

Limits: 11010000

Project(s): 45058115201(\*)

Federal Aid No: N/A

Total Roadway Length:	1.314 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	12/02/25
Total Proposal Length:	1.314 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$2,784,842.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of Milling & Resurfacing, Curb & Gutter, Sidewalk, and Signing/Pavement Markings on State Road 500 (US 441) from Lakeshore Boulevard to Lake Eustis Drive, approximately 1.314 miles in Lake County.

**PREQUALIFICATION REQUIRED**

**Call Order: 007 Proposal: E58F9**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (45058115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45058115201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	192.000
	0102- 60-	WORK ZONE SIGN	ED	5,210.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	48,960.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,373.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	360.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	900.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	900.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	23.000
	0107- 1-	LITTER REMOVAL	AC	31.630
	0107- 2-	MOWING	AC	31.630
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	384.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	31,541.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	31,050.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,645.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	985.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	913.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,677.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	7,326.900
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	460.000

**Call Order: 007 Proposal: E58F9**

ALT	Item	Description	Unit	Quantity
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	281.000
	0527- 2-	DETECTABLE WARNINGS	SF	829.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	33.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	75.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	2.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	6.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	6.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,136.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.110
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,143.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	2,294.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.630
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.230
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	74.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.310
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.620
	0908-333-100	HIGH FRICTION SURFACE COURSE	SY	1,898.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45058115201)	LS	1.000
<b>Section 0002 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,406.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	100.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45058115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,248.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	458.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	782.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.240
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	75.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	15.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	52.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.194
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,287.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.999

**Call Order: 007 Proposal: E58F9**

ALT	Item	Description	Unit	Quantity
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.318
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.422
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.363