

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	05250701	Call Order: 003	Proposal: E57F0	District:05
Counties:	ORANGE			
Road Name:	SR 527			
Limits:	75040102			
Project(s):	45057715201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.236 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	07/01/25	
Total Proposal Length:	0.236 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	

Proposal Budget Estimate: \$406,057.00

Please read the full advertisement

Description:  
SR 527 / ORANGE AVE FROM MAGNOLIA AVE TO SR 50 - PAVEMENT ONLY RESURFACE (FLEX)

The Improvements under this Contract consist of milling & resurfacing, curb & gutter, sidewalk, and signing and pavement markings on State Road 527 from Magnolia Ave. to SR 50 approximately 0.236 miles in Orange County.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtml>.

For more information about bidding on BDI projects, please see the training guide located at: <https://www.fdot.gov/equalopportunity/bdi.shtml>.

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtml>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year. Send a completed and notarized affidavit as an attachment to: [SmallBusiness@dot.state.fl.us](mailto:SmallBusiness@dot.state.fl.us).

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the projects major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://pdl.fdot.gov>.

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

**Call Order: 003 Proposal: E57F0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (45057715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45057715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	28.000
	0102- 60-	WORK ZONE SIGN	ED	1,625.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,900.000

**Call Order: 003 Proposal: E57F0**

ALT	Item	Description	Unit	Quantity
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	345.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	205.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	200.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	300.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	300.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.448
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.223
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	106.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.342
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	2.090
	0107- 2-	MOWING	AC	0.350
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	21.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	3,558.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,397.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	195.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	197.900
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	29.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	15.000
	0527- 2-	DETECTABLE WARNINGS	SF	88.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	100.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	173.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45057715201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	11.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	173.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	840.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45057715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	130.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	684.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	90.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.037

**Call Order: 003 Proposal: E57F0**

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	12.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	94.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.448
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.235
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.384