

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 08210511      Call Order: 004      Proposal: E8T16-R0      District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE

Road Name: SLOPE REHABILITATION - ZONE 1

Limits: Midpoint

Project(s): 19077445214(\*)      Federal Aid No: N/A

Total Roadway Length: 0.000 Miles      Contract Days: 365

Total Bridge Length: 0.000 Miles      Letting Date: 05/11/21

Total Proposal Length: 0.000 Miles      Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to repair and/or restore roadside slopes and back slopes, including site preparation, grading, borrow excavation material, sodding, and the installation of Geosynthetic soil reinforcement (Biaxial Geogrid) at various locations on the Homestead Extension Florida's Turnpike, Milepost (MP) 0.0 to 46.5, Florida's Turnpike, MP 0.0X to 100.0, and Sawgrass Expressway, MP 0.0 to 22.5.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

The Contractor shall perform all work during day hours in accordance with the Turnpike Lane Closure Policy.

Use products listed on the Department's Approved Product List (APL). Section 985 - Geosynthetic Materials.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

**Call Order: 004 Proposal: E8T16-R0**

| ALT  | Item       | Description                        | Unit | Quantity    |
|--|------------|------------------------------------|------|-------------|
| <b>Section 0001 MISCELLANEOUS ROUTINE MAINTENANCE (MH)</b> |            |                                    |      |             |
|  | 0120- 2- 2 | BORROW EXCAVATION, TRUCK MEASURE   | CY   | 1,600.000   |
|  | 0145- 1-   | GEOSYNTHETIC REINFORCED SOIL SLOPE | SF   | 300,000.000 |
|  | E575- 1-   | SODDING                            | SY   | 30,000.000  |
|  | E577- 70-  | SHOULDER REWORK                    | SY   | 30,000.000  |