

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	08250610	Call Order: 004	Proposal: E8W26-R0	District:08
Counties:	BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE			
Road Name:	Ramp Asphalt Maintenance - Zone 1			
Limits:	Midpoint			
Project(s):	44888717203(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	06/10/25	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

**Description:**

The work under this Contract consists of providing all labor, materials, equipment and incidentals necessary to perform maintenance and repair of ramp asphalt pavement, including replacing existing asphalt pavement, providing thermoplastic pavement markings, and raised pavement markers, at various locations on the Homestead Extension of Florida's Turnpike (SR 821 HEFT), Milepost (MP) 0.0 to 47.9, Florida's Turnpike (SR 91), MP 0.0x to 100.0 and the Sawgrass Expressway (SR 869) MP 0.0 to 21.8.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS CONTRACT

EXPERIENCE FORMS ARE REQUIRED. CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving. Experience in Landscaping Form (850-070-01) must be filled out and submitted with the bid. The form must be signed by the owner of the company or a company officer and dated in the space provided on the form.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 004 Proposal: E8W26-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	18,000.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	1,030.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	800.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	400.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	750.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	120.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	20.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	2.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	2.000
	E101- 1- 1	MOBILIZATION	LO	4.000
	E102- 1- 3	MAINTENANCE OF TRAFFIC (SITE SPECIFIC)	LO	4.000